

Tender No. PW-2026-04 for Dejong Road Bridge Rehabilitation & Charleville Road Bridge Rehabilitation



ADDENDUM NO.5

TENDER CLOSED: April 15th, 2026

ADDENDUM ISSUED: April 10th, 2026

This addendum is issued prior to receipt of tenders and shall be included as part of the Tender Submission.

This Addendum shall Amend, Clarify Questions or add to the Tender Documents as follows:

Questions and Answers:

Question 1: Special Provisions and Drawings for road section show Item #19 as HL3 and Item #20 as HL8 Hot Mix Asphalt, Bid form for Item #19 shows 60mm HL4 46.08t

Answer 1: Please see revised Bid Form.

Item #19 & Item 18 shall be HL4

Question 2: Special Provisions for Asphalt states payment by Square Meter

Answer 2: Item #19 Shall be paid by the ton & Item # 18 by the square meter

Question 3: There is no item for Asphalt Removal or Supply of granular on the Area South of the Bridge

Answer 3: Please see revised Bid Form.

Question 4: Item #20 – guiderail 20 meters seems too short.

Answer 4: End Treatments are a separate item as per detail OPD 922.161

Question 5: Item #21 - 3 tube railing on tender form says 110 meters, however we get approx. 24 meters

Answer 5: : Please see revised Bid form

Question 6: Item #24 - shows 1 m3 for concrete removals

Answer 6: Yes

Question 7: Item #29 – shows 2m3 for concrete form and pump (why an extra m3)

Answer 7: Please revised Bid Form

Question 8: Item #13 – is the deck scarification between the curbs only or to extend to the deck edge after existing curb removal?

Answer 8: Between Curbs

Question 9: Item #15 – is the new concrete deck exposed?

Answer 9: See Item #18 & 16

Question 10: Item #16 – is the waterproofing hot applied rubber or a spray on system. Section (06/S-1) shows sprayed on, however Item #18 states, there is asphalt on the deck.

Answer 10: Waterproofing shall be as per OPSS 914

Question 11: Item #21 – drawing section (05/S-3) shows a curb height of 200mm, is this before or after the asphalt is applied?

Answer 11: After

Question #12 Curb is 20 plus meters

Answer: Please see revised tender sheet

Question #13- Curb removal -Type A?

Answer: yes

Question #14 Excavation required

Answer: not required

Itemized Bid Form

Dejong Road Bridge Rehabilitation						
Item	OPSS / SP	Description	UNIT	QTY.	UNIT COST \$	TOTAL PRICE \$
1	SP	Mobilization and Demobilization	LS	1		
2	SP	Erosion and Sediment Control Including Turbidity Curtain	LS	1		
3	SP	Access to Work Area, Work Platform and Debris Containment	LS	1		
4	OPSS 706, SP	Temporary Advance Information Signs (TC-64)	ea.	2		
5	OPSS, 510, OPSS 180, SP	Removal of Existing Guide Rail System	LS	1		
6	OPSS 928, SP	Concrete Removal – Partial Depth – Type A	m3	0.5		
7	OPSS 928, SP	Concrete Removal – Partial Depth – Type B	m3	0.5		

8	OPSS 928, SP	Concrete Removal – Partial Depth – Type C	m3	0.5		
9	OPSS 930, SP	Concrete Patches – Form and Pump	m3	1.5		
10	OPSS 905, SP	Reinforcing Steel (Provisional)	m	5		
11	SP	Concrete Curb	m	21		
12	OPSS 932, SP	Crack Injection	m	4.5		
13	OPSS 928	Scarify Concrete Deck – 40mm	m2	110		
14	OPSS 929	Abrasive Blast Cleaning for Overlays	m2	110		
15	OPSS 930, OPSS 905 SP	Place Concrete Overlay with mesh & dowels– 80mm	m3	8.8		
16	OPSS 914	Bridge Deck Waterproofing	m2	110		
17	OPSS 308	Tack Coat	m2	110		
18	SP	Asphalt on Deck – 40mm HL4	m2	110		
19	SP	Asphalt – 60mm HL4 Surface	t	50		
20	OPSS 721, OPSD 912.185	Steel Beam Guide Rail	m	20		
21	OPSS 721, OPSS 912.450, SS110-37	Three Tube Railing on Curb, TL-4 and Associated Structure Connection	m	21		
22	OPSS 732	Supply and Install New Energy Attenuator End Treatment	ea.	2		
23	OPSD 912.255	Leaving End Treatment (Fish Tail Treatment)	ea.	2		
24A	180, 510	Asphalt Removal	M2	10		
24B	1010,206	Granular A	t	40		

Charleville Road Bridge Rehabilitation

Item	OPSS / SP	Description	UNIT	QTY.	UNIT COST \$	TOTAL PRICE \$
24	OPSS 928, SP	Concrete Removal – Partial Depth – Type C	m3	1		
25	OPSS 905, SP	Reinforcing Steel (Provisional)	m	5		
26	OPSS 929	Abrasive Blast Cleaning	m2	15		
27	OPSS 932, SP	Crack Injection	m	10		
28	SP	Expansion Joint Repair	m	6		
29	OPSS 930, SP	Concrete Patches – Form and Pump	m3	1		
				ITEMSTOTAL		
				HST		

TOTAL	
--------------	--

The Township of Augusta has the right to eliminate any or all sections of the project (in the itemized bid form) at any time after Tender Closing without penalty.

The Tenderer hereby offers to complete the work specified for Tender No. PW-2026-04 for the following prices:

Sub-Total	\$
HST	\$
TOTAL COST	\$

HST REGISTRATION NO. _____

End of Addendum

(A signed copy of this addendum must be included in Tender submission.)

I /WE hereby acknowledge receipt of this addendum.

Signed (must be Signing Officer of Firm)

Position

Name of Firm